

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-147-00765-00-00  
Spot: NENWNW Sec/Twnshp/Rge: 5-2S-18W  
4950 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: JACKSON A Well #: 5  
County: PHILLIPS Total Vertical Depth: 3442 feet

Operator License No.: 31569  
Op Name: BACH, JASON DBA BACH OIL PRODUC  
Address: RR 1, BOX 28  
PHILLIPSBURG, KS 67661

PROD Size: 5.5 feet: 3433 150 SX CMT  
SURF Size: 8.625 feet: 170 125 SX CMT

# 111 87

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/10/2004 9:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: JASON BACH Company: BACH, JASON DBA BACH OIL PRO Phone: (785) 476-5254

Proposed Plugging Method: Ordered 175 sxs Swift Multi-Density cement - 500# hulls - 15 sxs gel.  
Pulled tubing fish. WLM 3425'. TOF 800'+.  
Casing squeeze at 1225' w/200 sxs.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/10/2004 1:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Rigged up cementers to 5 1/2" casing - squeezed 16 sxs SMD with 200# hulls, followed with 15 sxs gel, followed with 80 sxs SMD with 200# hulls mixed in cement.  
Max. P.S.I. 400#. S.I.P. 200#.  
8 5/8" S.P. - squeezed 16 sxs SMD with 100# hulls.

Perfs:

RECEIVED  
JAN 11 2005  
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

Signed Dennis J Hamel  
(TECHNICIAN)

INVOICED

DATE 1-11-05  
INV. NO. 2005061049

NOV 24 2004

~~WADICED~~  
WADICED

B & R DRILLING & L B STABLEFORD #5 JACKSON 5-2-18W  
NE NW NW


Contr. B & R DRILLING, INC. PHILLIPS County

E 2187 Comm. 6-7-50 Comp. 7-28-50 IP 245 BOPD  
PHY POT

Tops	Depth	Datum
ANH	1740	+ 447
HEEB	3302	- 1115
LANS	3326	- 1139
T.D.	3442	- 1255

Casing  
8" 170 ACID 4000  
5" 3433 12 BOPH

HUFFSTUTTER POOL



INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS