

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-00792-00-00
Spot: NESESE Sec/Twnshp/Rge: 6-2S-18W
990 feet from S Section Line, 330 feet from E Section Line
Lease Name: IMM B Well #: 5
County: PHILLIPS Total Vertical Depth: 3430 feet

Operator License No.: 31569
Op Name: BACH, JASON DBA BACH OIL PRODUC
Address: RR 1, BOX 28
PHILLIPSBURG, KS 67661

PROD Size: 5.5 feet: 3430 150 SX CMT
SURF Size: 8.625 feet: 180 125 SX CMT

B 111 48'

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/10/2004 1:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JASON BACH Company: BACH, JASON DBA BACH OIL PRO Phone: (785) 476-5254

Proposed Plugging Method: Ordered 175 sxs Swift Multi-Density cement - 500# hulls - 15 sxs gel.
WLM 3400'. Casing squeeze at 1150' w/150 sxs.

Plugging Proposal Received By: DENNIS HAMEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/10/2004 2:30 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Rigged up cementers to 5 1/2" casing - squeezed 16 sxs SMD with 200# hulls mixed in cement, followed with 15 sxs gel, followed with 65 sxs SMD with 200# hulls.
Max. P.S.I. 1500#. S.I.P. 1500#.
Rigged up cementer to 8 5/8" S.P.
Squeezed 16 sxs SMD with 100# hulls.
S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3424	3427		
3409	3412		
3385	3388		
3364	3370		
3331	3335		

RECEIVED
JAN 11 2005
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

Signed Dennis L. Hamel
(TECHNICIAN)

INVOICED
DATE 1-11-05
INV. NO. 2005061049

NOV 23 2004

WADICEN

B & R DRILLING, INC.

#5 IMM B

6-2-18W
NE SE SE

6

Contr. _____ PHILLIPS _____ Coun

E 2181 Comm. _____ Comp. 2-2-51 IP 108 BOPD

Tops	Depth	Datum
ANH	1728	+ 453
LANS	3318	- 1137
T.D.	3430	- 1249

Casing
 8" 180 CO 3370
 5" 3430 PERF 3364-70
 ACID 2000
 SWB 3 BOPH

HUFFSTUTTER POOL

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS