

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-147-00794-00-02  
Spot: SWSESE Sec/Twnshp/Rge: 6-2S-18W  
330 feet from S Section Line, 990 feet from E Section Line  
Lease Name: IMM B Well #: 8  
County: PHILLIPS Total Vertical Depth: 3404 feet

Operator License No.: 31569  
Op Name: BACH, JASON DBA BACH OIL PRODUC  
Address: RR 1, BOX 28  
PHILLIPSBURG, KS 67661

PROD Size: 5.5 feet: 3404 150 SX CMT  
SURF Size: 8.625 feet: 174 100 SX CMT

\$110<sup>63</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/10/2004 12:00 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: JASON BACH Company: BACH, JASON DBA BACH OIL PRO Phone: (785) 476-5254

Proposed Plugging Method: Ordered 175 sxs Multi-Density cement -500# hulls.  
Tubing fish at 2480'. Rods & pump insert recovered from well.  
WLM at 2480'. TOF (11 seconds) 800' - 900'.  
Casing squeezes at 1200' - 1300' with 200 sxs; 2408' - 2440' w/200 sxs.

Plugging Proposal Received By: DENNIS HAMEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/12/2004 2:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Rigged up cementers to 8 5/8" S.P. - squeezed 16 sxs SMD with 100# hulls mixed in cement.  
Max. P.S.I. 300#. S.I.P. 100#.  
Rigged up cementers to 5 1/2" casing - squeezed 16 sxs SMD with 200# hulls, followed with  
125 sxs SMD with 200# hulls. P.S.I. 0#.  
November 12-2004 - Cement 6 - 7 seconds down.  
Rigged up cementers and pumped 9 barrels cement slurry to fill and squeeze casing.

Perfs:

Top	Bot	Thru	Comments
3394	3400		
3388	3391		
3378	3386		
3305	3316		
3287	3290		
2408	2440		
1200	1230		

RECEIVED  
JAN 11 2005  
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

Signed

*Dennis L. Hamel*

(TECHNICIAN)

NOV 23 2004

INVOICED  
DATE 1-11-05  
INV. NO. 2005061049


B & R DRILLING, INC. #8 IMM B 6-2-18W  
 SW SE SE 6

Contr. B & R DRILLING, INC. PHILLIPS County

E 2160RB Comm. Comp. 6-8-51 IP 90 BOPD  
 PHY POT

Tops	Depth	Datum
HEEB	3260	-1100
LANS	3286	-1126
T.D.	3404	-1244

Casing  
 8" 174  
 5" 3404  
 PERF 3394-3400,  
 3388-91,  
 3378-86,  
 ACID 1000: 8 G0/1/2 HR  
 PB 3367:  
 PERF 80 S, 3358-63  
 ACID 4000  
 1 1/2 BOPH & S WTR  
 PB 3327  
 HUFFSTUTTER POOL  
 PERF 3305-13  
 SWB 20 BOPH



INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

INDEXED  
 11/18/51