

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-00296-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 36-24S-15W
330 feet from S Section Line, 2310 feet from E Section Line
Lease Name: PRAEGER Well #: 1
County: STAFFORD Total Vertical Depth: 4401 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

PKR Size: feet: 4221
PROD Size: 5.5 feet: 4396 WITH 125 SX CMT
SURF Size: 8.625 feet: 276 WITH 225 SX CMT

#143⁰³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/04/2005 9:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 4080' & 5 SX CMT. PLUG AT 960' WITH 10 SX GEL - 50 SX CMT W/100# HULLS. PLUG AT 300' WITH 50 SX CMT W/100# HULLS. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/04/2005 12:35 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 4080' & 5 SX CMT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 960' WITH 10 SX GEL - 50 SX CMT W/100# HULLS. 2ND PLUG AT 300' WITH 50 SX CMT W/100# HULLS. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4396	4401	OH	
4168	4174		

RECEIVED
JAN 11 2005
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND ACID. RECOVERED 2220' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey
(TECHNICIAN)

INVOICED
DATE 1-11-05
INV. NO. 2005061053

Form CS-2/3