

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-125-01041-00-00
Spot: NWSENE Sec/Twnshp/Rge: 29-34S-15E
3530 feet from S Section Line, 1283 feet from E Section Line
Lease Name: COOK Well #: 2 OW
County: MONTGOMERY Total Vertical Depth: 1200 feet

Operator License No.: 32960
Op Name: YUKON PROPERTIES LLC
Address: 8419 FLORENCE AVE - SUITE D
DOWNEY, CA 90240

PROD Size: 4.5 feet: 1175
SURF Size: 7 feet: 50

39⁰⁰

Well Type: EOR UIC Docket No: E25168.1 Date/Time to Plug: 11/19/2004 8:00 AM
Plug Co. License No.: 33422 Plug Co. Name: RICK'S WELL SERVICE
Proposal Rcvd. from: RICK HOUSEL Company: RICK'S WELL SERVICE Phone: (620) 336-2944

Proposed Plugging Method: Run 2 inch tubing to bottom. Cement from bottom to top with with 2 gel spacers.

Plugging Proposal Received By: ALAN DUNNING Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/19/2004 5:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

2 inch pipe was inserted to bottom and gel circulated. 20 sacks of cement was spotted. The 2 inch was pulled to 800 ft. and 10 sacks of cement spotted. The 2 inch was pulled to 350 ft. and the well cemented to surface. A total of 85 sacks of portland cement was used to plug well.

Perfs:

RECEIVED
DEC 27 2004
KCC WICHITA

INVOICE
DATE 12-29-04
INV. NO. 200506085

RECEIVED
KCC DISTRICT #3

DEC 17 2004 AD

CHANUTE, KS

Remarks:

Plugged through: CSG

District: 03

Signed

Alan Dunning
(TECHNICIAN)