

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-20184-00-01
Spot: SE Sec/Twnshp/Rge: 29-34S-21W
1320 feet from S Section Line, 1320 feet from E Section Line
Lease Name: M C HARPER ETAL Well #: 3
County: CLARK Total Vertical Depth: 5600 feet

Operator License No.: 7744
Op Name: SHO-BAR ENERGY, INC.
Address: 215 E. 14TH
HARPER, KS 67058

CIBP Size: feet: 4100 WITH 2 SX CMT
CIBP Size: feet: 5462
PROD Size: 4.5 feet: 5600 WITH 250 SX CMT
SURF Size: 8.625 feet: 562 WITH 350 SX CMT

#182⁰⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/01/2004 9:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: CIBP @ 4100' WITH 2 SX CMT. PLUG AT 1000' WITH 50 SX CMT. PLUG AT 570' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/01/2004 12:01 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

1ST PLUG SET CIBP @ 4100' & 2 SX CMT. 2ND PLUG CASING PARTED AT 2700'. LAYED DOWN ON LOCATION. RAN 2 3/8" TUBING TO 1000' & CIRCULATED HOLE WITH MUD. PUMPED 50 SX CMT. 3RD PLUG PULLED TUBING TO 570'. LOAD HOLE WITH MUD & PUMPED 50 SX CMT. 4TH PLUG PULLED TUBING TO 40' & FILLED HOLE WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4316	4324		

RECEIVED
DEC 06 2004
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2700' OF 4 1/2" CASING.

Plugged through: TBG

District: 01

RECEIVED
DEC - 2 2004
MP
KCC Dodge City

Signed

Steve Durrant

(TECHNICIAN)

INVOICED

DATE 12.7.04
INV. NO. 2005060898