

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-21699-00-01  
Spot: N2S2SE Sec/Twnshp/Rge: 32-32S-34W  
1250 feet from S Section Line, 1320 feet from E Section Line  
Lease Name: HITCH H Well #: 2  
County: SEWARD Total Vertical Depth: 6394 feet

Operator License No.: 5447  
Op Name: OXY USA, INC.  
Address: 5 E. GREENWAY PLZ PO BOX 27570  
HOUSTON, TX 77227

CIBP Size: feet: 2580 WITH 2 SX CMT  
PROD Size: 5.5 feet: 2949 WITH 255 SX CMT  
SURF Size: 8.625 feet: 1714 WITH 455 SX CMT

#20781

Well Type: HI UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/29/2004 10:30 AM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 2580' WITH 2 SX CMT. PLUG AT 1750' WITH 25 SX CMT. PLUG AT 500' FILL WITH CMT TO SURFACE.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/29/2004 11:45 AM KCC Agent: STEVE DURRANT

Actual Plugging Report:

BOND LOG SHOWS 5 1/2" CEMENTED TO SURFACE. 1ST PLUG CIBP @ 2580' WITH 2 SX CMT. 2ND PLUG NO FLUID IN HOLE. FILLED HOLE TO 1750' & THEN PUMPED 25 SX CMT. 3RD PLUG FILLED HOLE TO 500'. PUMPED HOLE FULL OF CMT WITH 60 SX CMT. TESTED ANNULUS TO 1000 PSI.

Perfs:

Top	Bot	Thru	Comments
2714	2718		
2664	2670		
2635	2637		
2603	2607		

RECEIVED  
- RECEIVED  
JAN 07 2005  
KCC WIC  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED  
JAN - 3 2005  
KCC Dodge City

Signed

Steve Durrant

(TECHNICIAN)

INVOICED

DATE

1-7-05

INV. NO.

2005061037