

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-12790-00-01
Spot: NWSENE Sec/Twnshp/Rge: 12-25S-13W
1650 feet from N Section Line, 990 feet from E Section Line
Lease Name: NORTH LEESBURG UNIT Well #: 203
County: STAFFORD Total Vertical Depth: 4092 feet

Operator License No.: 6679
Op Name: SHORT, W.D. AND MARJORIE D/B/A SH
Address: PO BOX 1
OXFORD, KS 67119

PROD Size: 7 feet: 4078 WITH 240 SX CMT
SURF Size: 10.75 feet: 283 WITH 225 SX CMT

\$ 132⁹⁹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/20/2004 1:00 PM

Plug Co. License No.: 6679 Plug Co. Name: SHORT, W.D. AND MARJORIE D/B/A SHORT, W. D. OIL CO.

Proposal Rcvd. from: DON SHORT Company: W.D. SHORT OIL CO. Phone: (620) 455-3576

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

RECEIVED
JAN 06 2005
KCC WICHITA

Plugging Proposal Received By: RICHARD LACEY
Date/Time Plugging Completed: 12/21/2004 11:05 AM

WitnessType: COMPLETE (100%)
KCC Agent: RICHARD LACEY

Actual Plugging Report:

WELL HISTORY: DID BRADENHEAD SQUEEZE WITH 110 SX CMT. MAXIMUM PRESSURE 400 PSIG. SHUT IN PRESSURE 200 PSIG. SQUEEZED AT 810' WITH UNKNOW SX CMT. SQUEEZED @ 406' WITH 110 SX CMT. 09/20/04: RAN TUBING TO 3640' & PUMP 200# HULLS & 50 SX 60/40 POZMIX 6% GEL 3% CC. 11/08/04: RAN TUBING TO 750'. PUMPED 225 SX CMT. POOR CIRCULATION. DID NOT CIRCULATE CMT. 12/21/04: TAGGED CMT WITH TUBING @ 300'+/-. PULLED TUBING TO 260' & PUMPED 80 SX CMT. CIRCULATED CMT TO SURFACE. PULLED TUBING & TOPPED OFF 7" WITH 5 SX CMT.


Perfs:

Top	Bot	Thru	Comments
4032	4047		
3752	3762		
3727	3734		
3712	3716		
3681	3686		

Remarks: USED 60/40 POZMIX 4% GEL BY UNITED CEMENTING. NO CASING RECOVERED.

Plugged through: TBG

District: 01



Signed

Richard M. Lacey

(TECHNICIAN)

INVOICED

DATE 1-7-05

INV. NO. 2005061041

[Handwritten signature]