

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-20097-00-01
Spot: E2SWNE Sec/Twnshp/Rge: 18-33S-33W
3300 feet from S Section Line, 1830 feet from E Section Line
Lease Name: FREEMAN Well #: 2
County: SEWARD Total Vertical Depth: 4450 feet

Operator License No.: 6120
Op Name: CABOT OIL & GAS CORPORATION
Address: 600 17TH ST., SUITE 900 NORTH
DENVER, CO 80202

SURF Size: 8.625 feet: 1613 WITH 750 SX CMT

#144⁶³

Well Type: SWD UIC Docket No: D15874.0 Date/Time to Plug: 12/21/2004 1:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: LOAD HOLE, ESTABLIS INJECTION RATE BULLHEAD 200# & 25 SX CMT TO BOTTOM. MUD SPACER TO 550'. SPOT 40 SX CMT. MUD SPACER TO 40'. PUMP 25 SX CMT. NO RATE, PLUG THROUGH TUBING.

Plugging Proposal Received By: JIM HOLLAND WitnessType: NONE
Date/Time Plugging Completed: 12/21/2004 5:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

ESTABLISH RATE DOWN 8 5/8" @ 500 PSIG. PUMP 200# HULLS WITH 35 SX CMT TO PLUG BOTTOM. PUMP 30 BBL MUD SPACER TO 550' & PUMP 40 SX CMT. PUMP 23 BBL MUD SPACER TO 40'. PUMP 10 SX CMT TO SURFACE. ENDING PRESSURE 1500 PSIG.

Perfs:


Top	Bot	Thru	Comments
1145	1155		

RECEIVED
JAN 10 2005
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Jim Holland PERTT
(TECHNICIAN)

INVOICE

DATE 1-10-05

INV. NO. 2005061044

Form 10-27