

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25378-00-00
Spot: N2NENWNE Sec/Twnshp/Rge: 31-12S-17W
5230 feet from S Section Line, 1635 feet from E Section Line
Lease Name: KARLIN Well #: 1
County: ELLIS Total Vertical Depth: 3640 feet

Operator License No.: 6627

SURF Size: 8.625 feet: 284

Op Name: PROSPECT OIL & GAS CORP

Address: PO BOX 837
RUSSELL, KS 67665

#11830

Well Type: DH

UIC Docket No:

Date/Time to Plug: 12/29/2004 9:00 PM

Plug Co. License No.: 9431

Plug Co. Name: VONFELDT DRILLING, INC

Proposal Rcvd. from: DOUG BUDIG

Company: VONFELDT DRILLING, INC

Phone: (785) 483-1684

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.

Space all plugs with heavy drilling mud through drill pipe.

Base Dakota 721'. Anhy. 1317' - 1357'. RTD 3640'.

Arbuckle not cut - will call back. 01-06-2005 - no arbuckle cut.

Plugging Proposal Received By: RICHARD WILLIAMS

WitnessType: NONE

Date/Time Plugging Completed: 12/29/2004 11:00 PM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

1st. Plug at 1337' w/25 sxs.
2nd. Plug at 725' w/100 sxs.
3rd. Plug at 334' w/40 sxs.
4th. Plug at 40' w/10 sxs. 8 5/8" wiper plug.
Rathole with 15 sxs.
Mousehole with 10 sxs.

RECEIVED
JAN 10 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE 1-10-05

INV. NO. 2005061045

Form CP-2/3

JAN 06 2005