

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20417-00-01
Spot: NESE Sec/Twnshp/Rge: 12-32S-42W
1980 feet from S Section Line, 660 feet from E Section Line
Lease Name: HARRISON Well #: A1-12
County: MORTON Total Vertical Depth: 5350 feet

Operator License No.: 32782
Op Name: DUKE ENERGY FIELD SERVICES, LP
Address: 370 17TH ST., STE. 2500
DENVER, CO 80202

CIBP Size: feet: 3181 WITH 20 SX CMT
CIBP Size: feet: 5050 WITH 20 SX CMT
MSCC Size: feet: 3200
PROD Size: 4.5 feet: 5307 WITH 460 SX CMT
SURF Size: 8.625 feet: 1486 WITH 750 SX CMT

\$173⁸⁸

Well Type: GWI UIC Docket No: _____ Date/Time to Plug: 12/08/2004 1:00 PM
Plug Co. License No.: 7407 Plug Co. Name: EAGLE WELL SERVICE
Proposal Rcvd. from: RUSSELL BENTLEY Company: DUKE ENERGY FIELD SERVICES Phone: (303) 595-3331

Proposed Plugging Method: SET CIBP @ 5050' WITH 20 SX CMT. PERFORATE ZONE @ 3200'. SET CIBP @ 3150' WITH 20 SX CMT. PLUG AT 1500' WITH 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/08/2004 6:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

SET CIBP @ 5050' WITH 20 SX CMT ON TOP THROUGH TUBING. LOAD HOLE. PERFORATE & TEST GAS ZONE FROM 3262-72'. SET CIBP @ 3181' WITH 20 SX CMT ON TOP THROUGH TUBING. 1ST PLUG PULL OUT OF HOLE AT 1550'. LOAD HOLE WITH MUD & PUMP 50 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 600'. LOAD HOLE & PUMP 50 SX CMT. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 15 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5106	5118		

RECEIVED
DEC 16 2004
KCC WICHITA

Remarks: USED CLASS H CEMENT BY EAGLE WELL SERVICE. RECOVERED 1740' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
DEC 13 2004
KCC Dodge City

Signed

Jim Holland

(TECHNICIAN)

INVOICES
DATE 12-16-04
INV. NO. 2005060936