

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-21422-00-01  
Spot: S2S2NE Sec/Twnshp/Rge: 6-32S-33W  
2970 feet from S Section Line, 1320 feet from E Section Line  
Lease Name: ELLIS C Well #: 1  
County: SEWARD Total Vertical Depth: 5800 feet

Operator License No.: 5447  
Op Name: OXY USA, INC.  
Address: 5 E. GREENWAY PLZ PO BOX 27570  
HOUSTON, TX 77227

CIBP Size: feet: 4150 WITH 2 SX CMT  
CIBP Size: feet: 4590 WITH 2 SX CMT  
CIBP Size: feet: 4790 WITH 2 SX CMT  
CIBP Size: feet: 5008 WITH 2 SX CMT #188<sup>50</sup>  
COND Size: 20 feet: 80  
PROD Size: 5.5 feet: 5799 WITH 1075 SX CMT  
SURF Size: 8.625 feet: 1640 WITH 675 SX CMT

Well Type: GAS UIC Docket No: Date/Time to Plug: 12/30/2004 10:00 AM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 4150' WITH 2 SX CMT. RUN TUBING TO 1670'. PUMP 50 SX CMT. PLUG AT 690' WITH 78 SX CMT. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/30/2004 4:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

CIBP @ 4150' WITH 2 SX CMT. 1ST PLUG RUN IN HOLE WITH TUBING TO 1670'. HOLE FULL OF FLUID. PUMP 50 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE WITH TUBING TO 690'. PUMP 78 SX CMT TO SURFACE INSIDE 5 1/2" CASING. HOOK UP TO BACKSIDE. PUMP 17 SX CMT. PRESSURE TO 500 PSIG & SHUT IN.

Perfs:

Top	Bot	Thru	Comments
5541	5544		
5532	5537		
5478	5506		
5405	5454		
4799	4808		
4602	4612		
4185	4194		

RECEIVED  
JAN 12 2005  
KCC WICHITA

INVOICED  
DATE 1-12-05  
# 2005061058

RECEIVED  
JAN - 7 2005  
KCC Dodge City

Remarks: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED.

Plugged through: TBG

District: 01

INVOICED  
DATE 1-12-05  
# 2005061058

Signed

Jim Holland  
(TECHNICIAN)