

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-20843-00-01  
Spot: SESENE Sec/Twnshp/Rge: 24-34S-35W  
2310 feet from N Section Line, 330 feet from E Section Line  
Lease Name: HUDKINS C Well #: 1  
County: STEVENS Total Vertical Depth: 6638 feet

Operator License No.: 5447  
Op Name: OXY USA, INC.  
Address: 5 E. GREENWAY PLZ PO BOX 27570  
HOUSTON, TX 77227

CIBP Size: feet: 6190 WITH 2 SX CMT  
CIBP Size: feet: 6380 WITH 2 SX CMT  
COND Size: 20 feet: 35 WITH 3 YDS CMT  
PROD Size: 5.5 feet: 6634 WITH 200 SX CMT  
SURF Size: 8.625 feet: 1730 WITH 800 SX CMT

74  
#215

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/03/2005 8:00 AM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 300# HULLS & 25 SX CMT ON BOTTOM. PLUG AT 2900' WITH 80 SX CMT. PLUG AT 1760' WITH 50 SX CMT. PLUG AT 650' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/04/2005 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PBTD 6161'. PUMP 25 SX CMT & 300# HULLS. CIRCULATE HOLE WITH MUD. 1ST PLUG AT 2900' WITH 80 SX CMT. 2ND PLUG AT 1760' WITH 50 SX CMT. 3RD PLUG AT 650' WITH 30 SX CMT. 4TH PLUG AT 40-0' WITH 10 SX CMT. GOOD CIRCULATION ON ALL PLUGS.

Perfs:


Top	Bot	Thru	Comments
6418	6430		
6200	6214		
6126	6134		

RECEIVED  
JAN 12 2005  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 3014' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed \_\_\_\_\_

*Ken Jehlik*  
(TECHNICIAN)

INVOICED

DATE 1-12-05

INV. NO. 2005061058