

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-119-21124-00-00  
Spot: NESWSE Sec/Twnshp/Rge: 11-34S-26W  
990 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: THEIS B Well #: 2  
County: MEADE Total Vertical Depth: 6000 feet

Operator License No.: 5254  
Op Name: MIDCO EXPLORATION, INC.  
Address: 414 PLAZA DRIVE #204  
WESTMONT, IL 60559

CIBP Size: feet: 2745 WITH 2 SX CMT  
COND Size: 20 feet: 30 WITH 40 SX CMT  
PROD Size: 4.5 feet: 2992 WITH 165 SX CMT  
SURF Size: 8.625 feet: 757 WITH 425 SX CMT

\$195<sup>00</sup>

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/28/2004 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: DAVID MAYFIELD Company: MIDCO EXPLORATION Phone: (630) 655-2198

Proposed Plugging Method: CIBP WITHIN 50' OF PERF - SPOT 2 SX, PULL UP TO 1200' - 50 SX, PULL UP T 30' BELOW SURFACE (APPROX. 817') 50 SX PULL UP TO 40' - CEMENT TO SURFACE. 10 SX. (VERBALLY APPROVED BY DODGE CITY FIELD OFFICE.)

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/28/2004 11:30 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 2934'. SET CIBP @ 2745' WITH 2 SX CMT ON TOP. 1ST PLUG PULL OUT OF HOLE TO 1240'. PUMP 10 SX GEL FOLLOWED BY 50 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 840'. LOAD HOLE & PUMP 50 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2783	2787		

RECEIVED  
JAN 12 2005  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2060' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED  
JAN - 7 2005  
KCC Dodge City

Signed Jim Holland PIRT#  
(TECHNICIAN)

INVOICE  
DATE 1-12-05  
INV. NO. 2005061057

Form CP26