

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-187-20812-00-00
Spot: NWSESE Sec/Twnshp/Rge: 25-29S-40W
900 feet from S Section Line, 1300 feet from E Section Line
Lease Name: RYAN PATRICK Well #: 1-25
County: STANTON Total Vertical Depth: 5765 feet

Operator License No.: 5952
Op Name: BP AMERICA PRODUCTION COMPANY
Address: 2225 WEST OKLAHOMA AVENUE
ULYSSES, KS 67880

CIBP Size: feet: 2851
CIBP Size: feet: 5530 WITH 2 SX CMT
MSCC Size: feet: 2823 WITH 450 SX CMT
PROD Size: 4.5 feet: 5684 WITH 635 SX CMT
SURF Size: 8.625 feet: 1572 WITH 615 SX CMT

3/6
4/87

Well Type: GAS UIC Docket No: Date/Time to Plug: 12/29/2004 10:00 AM
Plug Co. License No.: 99997 Plug Co. Name: HALLIBURTON ENERGY SERVICES
Proposal Rcvd. from: KEVIN STRUBE Company: BP AMERICA Phone: (620) 356-6955

Proposed Plugging Method: PERFORATE & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/29/2004 11:30 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:

LEFT IN HOLE: TOP OF FISH @ 5560' WITH TBG ANCHOR @ 5575' WITH 3 JOINTS OF TUBING & SEAT NIPPLE BELOW ANCHOR. DV TOOL @ 2823' WITH 450 SX CMT. SET CIBP @ 5530' WITH 2 SX CMT. SET CIBP @ 2851' & LOAD HOLE. PERFORATE @ 950'. PUMP 202 SX CMT TO FILL 4 1/2" & 8 5/8" X 4 1/2" ANNULUS FROM 950' TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
5616	5622		

RECEIVED
JAN 12 2005
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY HALLIBURTON. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Jim Holland
(TECHNICIAN)

INVOICED

DATE 1-12-05
2005061056

Form CP-23