



15-039-20272-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 18 1973

CONSERVATION DIVISION
Wichita, Kansas

7-18-73

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. George Stoepfelwerth of Stoepfelwerth Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Stoepfelwerth guarantees payment of the plugging fee.

Operator's full Name: Indigo Oil Company,

Complete Address: ~~2713 East Akron, Mesa, Arizona.~~ INCORRECT

Lease Name: Anderson Well No. 1

Location: CE/2-SE-NE Sec. 7 Twp. 5 Rge. (E)(W) 29

County: Decatur Total Depth 4133' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Stoepfelwerth was instructed to plug the well as follows:

212'--8 5/8" Surface casing, cement circulated.

Top of Dakota section @ 1360'.

Circulate hole with heavy mud. Pull DP to 1600' and displace 110 Cu. Ft. cement thru DP. Pull DP to 215' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

K. L. Nichols

Conservation Division Agent