

State of Kansas



15-039-00580-00-00

FORM - CP-2  
Rev. 9-8-64

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUL 7 1965  
7-7-65  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. D. B. Pulley of Forbes Casing Pulling, Inc. has this  
date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Continental Oil Company,

Complete Address: Box # 267, Great Bend, Kansas.

Lease Name: G. Gillespie Well No. A-2

Location: SW-NE-SE Sec. 27 Twp. 5 Rge. (E) (W) 27

County Decatur Total Depth 3720 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Pulley was instructed to plug the well as follows:

240' -- 10 3/4" Surface pipe, cement circulated.  
3720' -- 5 1/2" Production casing. Well plugged back to 3683,  
Top perforations @ 3648'.

Sand well back to 3635' and set 5 Sx. cement with dump bailer.  
Pull 5 1/2" casing to 600' and circulate heavy gel mud. Pull  
5 1/2" to 540' and displace 25 Sx. cement thru 5 1/2". Pull 5 1/2" to  
240' and displace 25 Sx. cement thru 5 1/2". Pull 5 1/2", set rock  
bridge @ 35' and 15 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent