


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15-153-30134-00-00  
WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Rawlins County, Sec. 14 Twp. 5S Rge. 35 (E) (W) **x**

Location as "NE/CNW%SW%" or footage from lines C NW SW  
Lease Owner Empire Drilling Company  
Lease Name Brewster Well No. 1  
Office Address 650 Fourth National Bank Building, Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed April 9, 1961 19  
Application for plugging filed April 9, 1961 19  
Application for plugging approved April 9, 1961 19  
Plugging commenced April 9, 1961 19  
Plugging completed April 9, 1961 19  
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4835 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Shale	0	130			
	Sand-Shale	130	280	8 5/8"	262'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

**Plug set at 400' with 20 sacks cement.**  
**Plug set at 260' with 20 sacks cement.**  
**Plug set at 40' with 10 sacks cement.**

**RECEIVED**  
STATE CORPORATION COMMISSION

APR 20 1961

CONSERVATION DIVISION  
Wichita, Kansas

4-20-61

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Empire Drilling Company  
Address 650 Fourth National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Dan J. Kornfeld (~~employee of owner~~) (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
650-4th Nat\*1. Bank Bldg., Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of April, 19 61

[Signature]  
Lucille H. Harr  
Notary Public.

My commission expires October 21, 1962



15-53-30134-00-00

LOG

**RECEIVED**  
STATE CORPORATION COMMISSION

APR 20 1961

CONSERVATION DIVISION  
Wichita, Kansas

420-61

COMPANY: Empire Drilling Company  
 CONTRACTOR: Empire Drilling Company  
 FARM: Brewster # 1  
 LOCATION: C NW SW Section 14-5S-35W, Rawlins County, Kansas  
 COMMENCED: March 27, 1961  
 COMPLETED: April 9, 1961

ELEVATION: 3228 KB  
POTENTIAL: D & A

\*\*\*\*\*

0	to	130	Shale
130	to	280	Sand-Shale
280	to	1935	Shale
1935	to	2283	Shale-Shells
2283	to	2495	Shale-Shells-Pyrite
2495	to	2902	Shale-Shells
2902	to	2940	Anhydrite
2940	to	3285	Shale-Shells
3285	to	3353	Shale
3353	to	3460	Shale-Shells
3460	to	3825	Shale-Lime
3825	to	3880	Lime
3880	to	4015	Lime-Shale
4015	to	4078	Lime
4078	to	4220	Lime-Shale
4220	to	4275	Lime
4275	to	4315	Lime-Shale
4315	to	4375	Lime
4375	to	4485	Lime-SHALE
4485	to	4535	Lime-Shale-Chert
4535	to	4580	Lime
4580	to	4601	Lime-Shale
4601	to	4700	Lime
4700	to	4755	Shale-Lime
4755	to	4805	Lime-Chert
4805	to	4835	Mississippi
4835			Rotary Total Depth

SET: 262\* 8 5/8" casing with 115 sacks cement.

ELECTRIC LOG TOPS:

Howard Lime	3863	- 635
Topeka	3902	- 674
Heebner	4075	- 847
Toronto	4110	- 882
Lansing	4126	- 898
Base Kansas City	4392	-1164
Cherokee Group	4598	-1370
Mississippian	4800	-1572
Schlumberger TD	4832	

\*\*\*\*\*

CERTIFICATION

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log on the Brewster # 1, C NW SW Sec. 14-5S-35W, Rawlins County, Kansas, as reflected by the files of Empire Drilling Company.

*Dan J. Kornfeld*  
\_\_\_\_\_  
DAN J. KORNFELD

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 18th day of April, 1961.

*Lucille H. Harr*  
\_\_\_\_\_  
LUCILLE H. HARR, Notary Public

My commission expires Oct. 21, 1962.