


15-153-30132-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Flat

Rawlins County. Sec. 3 Twp. 5s Rge. 35 (E) (W) **x**  
Location as "NE/CNW/SW" or footage from lines C SW NW  
Lease Owner Empire Drilling Company  
Lease Name Dewey Well No. 1  
Office Address 650 Fourth National Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed March 27, 1961 19  
Application for plugging filed March 27, 1961 19  
Application for plugging approved March 27, 1961 19  
Plugging commenced March 27, 1961 19  
Plugging completed March 27, 1961 19  
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4755 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	<u>Sand-Shale</u>	<u>0</u>	<u>222</u>	<u>8 5/8"</u>	<u>199"</u>	<u>-0-</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

**Plug set at 400' with 20 sacks cement**  
**Plug set at 190' with 20 sacks cement**  
**Plug set at 40' with 10 sacks cement**

RECEIVED  
STATE CORPORATION COMMISSION  
APR 7 1961  
CONSERVATION DIVISION  
Wichita, Kansas 4-7-61

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Empire Drilling Company  
Address 650 Fourth National Bank Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Dan J. Kornfeld (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
650-4th Nat'l. Bank Bldg, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of April, 19 61

My commission expires October 21, 1962.  
Lucille H. Harr Notary Public.



15-53-30132-00-00

LOG

COMPANY: Empire Drilling Company  
 CONTRACTOR: Empire Drilling Company  
 FARM: Dewey # 1  
 LOCATION: C SW NW Section 3-5S-35W, Rawlins County, Kansas  
 COMMENCED: March 13, 1961  
 COMPLETED: March 27, 1961

ELEVATION: 3183 KB  
 POTENTIAL: D & A

\* \* \* \* \*

0	to	222	Sand-Shale
222	to	1015	Shale-Shells
1015	to	1850	Shale
1850	to	2050	Shale-Gypsum
2050	to	2235	Shale-Shells
2235	to	2500	Shale-Sand-Shells
2500	to	2725	Shale-Shells
2725	to	2736	Shale
2736	to	2767	Anhydrite
2767	to	2876	Shale
2876	to	2912	Anhydrite
2912	to	3320	Shale-Shells
3320	to	3550	Shale
3550	to	4195	Lime-Shale
4195	to	4230	Lime
4230	to	4295	Lime-Shale
4295	to	4341	Lime
4341	to	4420	Shale-Lime
4420	to	4450	Lime
4450	to	4495	Lime-Chert
4495	to	4570	Chert-Lime
4570	to	4686	Lime-Shale
4686	to	4741	Mississippi
4741	to	4755	Mississippi-Chert
4755			Rotary Total Depth

RECEIVED  
STATE CORPORATION COMMISSION

APR 7 1961

CONSERVATION DIVISION  
Wichita, Kansas

4-7-61

SET: 199" 8 5/8" casing with 115 sacks cement.

ELECTRIC LOG TOPS:

Howard Lime	3824	- 641
Topeka	3864	-681
Heebner	4032	- 849
Toronto	4067	- 884
Lansing	4081	- 898
Base Kansas City	4342	-1159
Cherokee Group	4555	-1372
Mississippian	4704	-1521
Schlumberger TD	4758	

\* \* \* \* \*

CERTIFICATION

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log on the Dewey # 1, C SW NW Section 3-5s-35w, Rawlins County, Kansas, as reflected by the files of Empire Drilling Company.

*Dan J. Kornfeld*  
 \_\_\_\_\_  
 DAN J. KORNFELD

Subscribed and sworn to before me, a Notary Public within and for Sedgwick County, Kansas, this 6th day of April, 1961.

*Lucille H. Harr*  
 \_\_\_\_\_  
 Lucille H. Harr, Notary Public

My commission expires Oct. 21, 1962.