

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

15-153-20394-00-01

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Rawlins SEC. 5 TWP. 5 RGE. 34 ~~33~~/W
 Location as in quarters or footage from lines:
2200' FSL & 2200' FWL of SW/4

	x		

Locate Well
 correctly on above
 Section Platt.

Lease Owner S & W Drilling Co., Inc.
 Lease Name Denny Well No. 1
 Office Address Box 132 Oberlin, Kansas 67749
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry
 Date Well Completed Oct. 28, 1982
 Application for plugging filed Nov. 5, 1982
 Plugging commenced Oct. 28, 1982
 Plugging completed Oct. 28, 1982
 Reason for abandonment of well or producing formation Rotary dry & abn.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt

Producing formation none Depth to top bottom T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
fresh water						
sand	fresh water	40	140	8 5/8	257	none

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from feet
 to feet for each plug set.

At 2850 spot 20 sx, displace with mud; at 1710 spot 100sx, displace with mud;
 at 270 spot 40 sx, displace with mud; at 40 plug with 8 5/8 plug and sack cottonseed
 hulls followed by 10 sx in 8 5/8 and 10 sx in rathole. All 180 sx cement 50/50 Poz
 with 6% gel and 3% CC.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services

STATE OF KANSAS COUNTY OF DECATUR, ss.

HELEN BEALL, VICE PRESIDENT (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) Helen Beall
BOX 132 OBERLIN, KAN 67749
 (Address)

SUBSCRIBED AND SWORN TO before me this 16 day NOV, 19 82

Herbert M. Beaman
 Notary Public.

My Commission expires: 12/12/1984

NOV 17 1982
 CONSERVATION DIVISION
 Wichita, Kansas

