


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15-153-00005-00-00  
WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Rawlins County. Sec. 32 Twp. 5S Rge. 33 ~~XXX~~ ~~XXX~~ (W)  
Location as "NE/CNW/SW" or footage from lines SW<sub>1/4</sub>-NE<sub>1/4</sub>  
Lease Owner Jackson, Shear & Parker  
Lease Name Grover Well No. 1  
Office Address Duncan, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed September 13 1958  
Application for plugging filed September 12 1958  
Application for plugging approved September 12 1958  
Plugging commenced September 13 1958  
Plugging completed September 13 1958  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fabricius  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4940 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface soil, clay		0	30			
Sand and Shale		30	250			
Shale		250	304	8-5/8	304	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole full of heavy mud from T.D. to 600'  
1/3 sack of hulls, rolled in sack @ 600'  
Halliburton plug @ 600'  
20 sacks cement mixed through drill pipe, placed on plug.  
Heavy mud to 300'  
1/3 sack of hulls rolled in sack @ 300'  
Halliburton plug @ 300'  
20 sacks of cement mixed through drill pipe, placed on plug.  
Heavy mud to within 40 feet of surface.  
Halliburton plug @ 40'  
10 sacks cement from plug to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Badger Drillers, Inc.  
Address Box 287, Tulsa, Oklahoma

STATE OF Oklahoma COUNTY OF Stephens, ss.  
Miles Jackson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) Miles Jackson  
Box 149, Duncan, Okla. (Address)

SUBSCRIBED AND SWORN TO before me this 25th day of September, 1958

My commission expires June 26, 1962

PLUGGING  
FILE SEC. 32 T. 5 R. 33  
BOOK PAGE 131 LINE 33

STATE CORPORATION COMMISSION  
SEP 26 1958  
Notary Public  
Conservation Division  
Wichita, Kansas  
9-26-58