

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

API Number 15 - 039 - 20,433 - 00 - 00 (of this well)
Lease Owner Nelson Petroleum Company
Address 2301 Fourth National Bank, Tulsa, Oklahoma 74119
Lease (Farm Name) EVERETT G. SHULER Well No. 1
Well Location NE SW NE Sec. 29 Twp. 5S Rge. 29W (E) (W) X
County Decatur Total Depth 4450' Field Name _____
Oil Well X Gas Well _____ Input Well _____ SWD Well _____ Rotary D & A _____
Well Log attached with this application as required Yes
Date and hour plugging is desired to begin As soon as puller is available

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Kelso Casing Pulling Address Box 176, Chase Kansas 67524
Kelso Casing Pulling 683
Plugging Contractor Abercrombie Drilling, Inc. License No. _____
Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:

Name Nelson Petroleum Company
Address 2301 Fourth National Bank, Tulsa, Oklahoma 74119

and payment will be guaranteed by applicant or acting agent.

Signed: Jack L. Partridge
Applicant or Acting Agent
Jack L. Partridge
Date: December 20, 1978

RECEIVED
STATE CORPORATION COMMISSION
DEC 21 1978
12-21-78
CONSERVATION DIVISION
Wichita, Kansas

CONTRACTOR'S WELL LOG

OPERATOR:
 CONTRACTOR:
 WELL NAME:
 LOCATION:
 SPUD DATE:
 COMPLETION DATE:

15-039-20433-00-00

Nelson Petroleum Company
 Abercrombie Drilling, Inc.
 Everett Shuler #1
 NE SW NE, Section 29-5S-29W
 Decatur County, Kansas
 November 18, 1978
 November 29, 1978

0	310	Surface soil, sand & shale
310	340	Shale
340	2253	Shale & sand
2253	2543	Shale
2543	2574	Anhydrite
2574	3005	Shale
3005	3330	Lime & shale
3330	3485	Shale
3485	3807	Lime & shale
3807	3900	Shale & lime
3900	4045	Shale
4045	4370	Lime
4370	4450	Lime & shale
	4450	Rotary Total Depth

Spud hole at 5:00 p.m., November 18, 1978. Drilled 310' of 12 1/4" hole. Ran 7 joints of 8 5/8" - 28# casing. Set at 307' K.B. with 225 sacks of 60/40 posmix, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 10:30 p.m., November 18, 1978.

T.D. 4450'. Ran 104 joints of new 4 1/2" - 10 1/2# casing. Set at 4155' with 25 sacks of Halliburton Lite followed with 200 sacks of 50/50 posmix, 18% salt saturated, 3/4 of 1% CFR-2. Job was complete at 3:30 p.m., November 29, 1978.

SAMPLE TOPS:

Anhydrite 2543'
 B/Anhydrite 2574'

RECEIVED
 STATE CORPORATION COMMISSION

DEC 21 1978

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

CONSERVATION DIVISION
 Wichita, Kansas


12-21-78

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Everett Shuler #1, NE SW NE, Section 29-5S-29W, Decatur County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
 Jack L. Partridge
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid as of this 6th day of December, 1978.



Sherrie L. Brooks
 Sherrie Brooks, Notary Public

My commission expires 8-21-82.

State of Kansas



15-039-20433-06-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

December 21, 1978

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Everett G. Shuler
Description	NE SW NE Sec. 29-5-29W
County	Decatur
Total Depth	4450
Plugging Contractor	Kelso Casing Pulling


Nelson Petroleum Co.
2301 Fourth National Bank Building
Tulsa, Oklahoma 74119

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,


J. Lewis Brock, Administrator

Mr. ~~Gilbert Belthazer, P.O. Box 9, Route #1, Falco, Kansas~~ 67657
is hereby assigned to supervise the plugging of the above
named well.