

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

RECEIVED
STATE CORPORATION COMMISSION
WEC 7-7-88
7 1988

WELL PLUGGING APPLICATION FORM
(File One Copy)

15-039-00058-00-01

API NUMBER February 2, 1968 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Burch Exploration Inc. OPERATORS LICENSE NO. 7448

ADDRESS 1225 Edinburgh Way Parker, Co. 80134 PHONE # (303) 841-9417

LEASE (FARM) Feeley WELL NO. 5 SWD WELL LOCATION NW-NE-NE COUNTY DECATUR

SEC. 27 TWP. 55 RGE. 27W (E) or (W) TOTAL DEPTH 3913 PLUG BACK TD 3870

Check One:

OIL WELL _____ GAS WELL _____ D & A _____ SWD or INJ WELL SWD DOCKET NO. _____

SURFACE CASING SIZE 8 5/8 SET AT 250 CEMENTED WITH 210 SACKS

CASING SIZE 4 1/2 SET AT 3912 CEMENTED WITH 425 SACKS

PERFORATED AT 3850 To 3854, 3792 To 3796 + 3650 To 3756

CONDITION OF WELL: GOOD _____ POOR _____ CASING LEAK X JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Mix 300 lbs. of Hulls on first 200 lbs. of cement

to plug off perforations. Fill casing to surface with 140 sacks of cement. Pressure
to 300 lbs. Mix 40 sacks pump down 8 5/8 casing. Pressure to 400 lbs.
(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? _____
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN April 15, 1988

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Melvin L. Taylor PHONE # (308) 345-3214

ADDRESS 802 East 6th street McCook, NE 69001

PLUGGING CONTRACTOR Joe's Well Service LICENSE NO. 6779

ADDRESS P.O. Box 115 Oberlin, KS 67749 PHONE # (913) 475-3422

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: J. David Burch
(Operator or Agent)

DATE: 12/1/88