

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 129-10266-00-01 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 01/26/1951

Well Operator: Colorado Interstate Gas Company KCC License #: 7117
(Owner / Company Name) (Operator's)

Address: P. O. Box 1087 City: Colorado Springs

State: Colorado Zip Code: 80944 Contact Phone: (719) 520 - 4557

Lease: Boehm Well #: 1 Sec. 14 Twp. 33 S. R. 42 East West

NE - NW Spot Location / QQQQ County: Morton

4,950 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

3,030 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: Gas Storage Well

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 13" Set at: 260' GL Cemented with: 250 Sacks

Production Casing Size: 5-1/2" Set at: 5,030' GL Cemented with: 150 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perfs: 4,784-96(Sqzd.), 4,842-68(Open), 4,876-82(Sqzd.), 4,892-96(Sqzd.), 4,922-26(Sqzd.)

CIBP @ 4,872'. All depths GL.

Elevation: 3,485' (G.L. / K.B.) T.D.: 5,987' PBTD: 4,872' Anhydrite Depth: 1,396'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): _____

See Attachment.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? It was filed previously with original CP-1 that has since expired.

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: David Veatch

Phone: (970) 376 - 1273

Address: P. O. Box 615 City / State: Fort Morgan, CO 80723

Plugging Contractor: Eagle Services, Inc. KCC License #: 7407
(Company Name) (Contractor's)

Address: 1661 West 7, Liberal, KS 67901 Phone: (620) 482 - 5637

Proposed Date and Hour of Plugging (if known?): Unknown

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 1/12/05 Authorized Operator / Agent: [Signature]
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

8/05

6/05

RECEIVED
JAN 18 2005
KCC WICHITA

15-129-10266-00-01

Boehm 1

Preliminary procedure confirmed w/ KCC, Steve Durrant 03/12/04

Dig out around wellhead to expose 13" x 8-5/8" casing interface. If there are outlets then rig to circ., otherwise fill back in.
Pump 300# hulls + 40 sk cmt to bottom
Use 36 viscosity, 9# mud between plugs in open-hole sections
Free-point 5-1/2" casing and cut off at _____ ft
Spot 50 sk plug on stub at _____ ft
Pull casing to 2711'
Pump 50 sk plug at 2711'
Lay down 5-1/2" casing
Free-point 8-5/8" casing and cut off at _____ ft
Lay down 8-5/8" casing
Run tubing to 8-5/8" casing stub
Spot 50 sk plug on stub at _____ ft
Pull tubing to _____ ft
Spot _____ sk plug from _____ ft to _____ ft
Pull tubing to 25 ft
Spot 25 ft plug from 25 ft to surface
Cut off 13" casing 5' below grade and weld on cap.

RECEIVED
JAN 18 2005
KCC WICHITA

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Colorado Interstate Gas Company
PO Box 1087
Colorado Springs, CO 80944

January 19, 2005

Re: BOEHM #1
API 15-129-10266-00-01
NENENW 14-33S-42W, 4950 FSL 3030 FEL
MORTON COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888

Sincerely


David P. Williams
Production Supervisor