

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-153-20,717-00-00

LEASE NAME Briney "A"

WELL NUMBER 1

1320 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 29 TWP. 5S RGE. 36 ~~(E) (W)~~

COUNTY Rawlins

Date Well Completed 7-4-88

Plugging Commenced 7-4-88

Plugging Completed 7-5-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR A. L. Abercrombie, Inc.

ADDRESS 801 Union Center, Wichita, KS 67202

PHONE# (316) 262-1841 OPERATORS LICENSE NO. 5393

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-5-88 (date)

by District 6, Hays, KS. State Plugger Gilbert Balthzar (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4940

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	364	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Pump mud to 3130', 1st plug from 3130' to 3030' w/25 sx; pump mud to 2240', 2nd plug from 2240' to 1840' w/100 sx; pump mud to 380', 3rd plug from 380' to 220' w/40 sx; pump mud to 40', 4th plug from 40' to surface w/10 sx; 10 sx. in mousehole and 15 sx. in rathole. All cement 60/40 posmix, 6% gel.

(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 801 Union Center, Wichita, KS 67202 STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss. JUL 12 1988
7-12-88

Jack K. Wharton (Employee of Operator or Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 801 Union Center
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 11th day of July, 19 88

Janet A. Stuck
Notary Public

My Commission Expires: 12-29-90

