

15-023-20208-00-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Cheyenne SEC. 3 TWP. 5S RGE. 37 E/W
 Location as in quarters or footage from lines:
C NE NW

	+		
		3	

Locate Well
 correctly on above
 Section Platt.

Lease Owner Cities Service Oil & Gas Corporation
 Lease Name Fleming "A" Well No. 1
 Office Address 800 Sutton Place 209 E. William Wichita, Ks. 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry
 Date Well Completed 1-21-84
 Application for plugging filed 1-21-84
 Plugging commenced 1-21-84
 Plugging completed 1-21-84
 Reason for abandonment of well or producing formation _____

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow
 Producing formation _____ Depth to top _____ bottom T.D. 4715'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	374'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

- Spotted 20 sx. cement @ 3050' thru drill pipe.
- Spotted 100 sx. cement @ 2150' thru drill pipe.
- Spotted 40 sx. cement @ 370' thru drill pipe.
- Spotted 10 sx. cement @ 40' thru drill pipe.
- Spotted 10 sx. cement in rathole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor White & Ellis Drilling, Inc.
401 E. Douglas, Suite 500, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Ernest Sifford (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) Ernest Sifford
401 E. Douglas #500 Wichita
 (Address) Kansas 67202


SUBSCRIBED AND SWORN TO before me this 26th day of Jan, 19 84

My Commission expires _____


David F. Jamis
 David F. Jamis, Notary Public.

RECEIVED
 STATE CORPORATION COMMISSION

JAN 27 1984
1-27-84
 CONSERVATION DIVISION
 Wichita, Kansas



15-023-20208-00-00

WHITE

AND ELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: Cities Service Oil & Gas Corporation 800 Sutton Place 209 E. William, Wichita, Ks. 67202

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500, Wichita, Ks. 67202

Lease Name Flemming "A" Well No. 1

Sec. 3 T. 5S R. 37W Spot C NE NW

County Cheyenne State Kansas Elevation _____

Casing Record:

Surface: 8 5/8" @ 374' with 255 sx.

Production: _____ @ _____ with _____ sx.

Type Well: D & A Total Depth 4715'

Drilling Commenced 1-11-84 Drilling Completed 1-21-84

Formation	From	To	Tops
Cellar	0	7	
Sand, Shale	7	728	
Lime, Shale	728	1553	
Shale	1553	2180	
Shale, Lime	2180	2633	
Lime, Shale	2633	2770	
Shale	2770	3037	
Shale, Lime	3037	3871	
Lime, Shale	3871	4150	
Shale, Lime	4150	4247	
Lime	4247	4460	
Shale, Lime	4460	4542	
Lime, Shale	4542	4633	
Shale, Lime	4633	4715	

RECEIVED
STATE CORPORATION COMMISSION
1-27-84
JAN 27 1984
CONSERVATION DIVISION
Wichita, Kansas

Well Log
Flemming "A" #1
Cheyenne County, Kansas

Heebner	4149'	(- 825')
Lansing	4201'	(- 878')
Base Kansas City	4471'	(-1147')
Marmaton	4485'	(-1161')
RTD	4715'	