

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED  
STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-039-20272-00-00

JUL 18 1973  
CONSERVATION DIVISION  
Wichita, Kansas

7-18-73

Operator's Full Name Indigo Oil Company,

Complete Address ~~2713 East Akron, Mesa, Arizona.~~ IN CORRECT

Lease Name Anderson Well No. 1

Location CE/2-SE-NE Sec. 7 Twp. 5 Rge. (E) (W) 29

County Decatur Total Depth 4133'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Stoepelwerth Drilling, Incorporated,

Address 2005 Norris, McCook, Nebraska. License No.       

Operation Completed: Hour 6:00 PM Day 15 Month 7 Year 1973

The above well was plugged as follows:

212'--8 5/8" Surface casing, cement circulated.  
Top of Dakota section @ 1360'.

Circulated hole with heavy mud. Pulled DP to 1600' and displaced 110 Cu. Ft. cement thru DP from 1600' to 1275'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: A. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 7/18/73  
INV. NO. 7648-W