

DISTRICT CONSERVATION AGENT'S REPORT

R

15-039-19050-00-~~108~~
01

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 14-20

LOCATION NE NE SW

SEC. 35 TWP. 5 RGE. 29

Dry Hole Abandoned Oil Well Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 1 Lease Wackendorfer

Operator Henderson Oil Co Address Wichita, Kans

Field _____ County Decatur

Total Depth 4192 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 200' circulated with cement - 5 1/2" at 4190' with
150 sax cement behind - Lane Wells plugs to 4102' perforated at
4089'.

Sand to 4070', set 4 sax cement with dump bailer, pulled 1475'
5 1/2" - mud to 200', set rock and 15 sax cement, mud to 55', set
rock and 10 sax cement to bottom cellar.

PLUGGING
FILE SEC 35 T 5 R 29 W
BOOK 14 PAGE 20

[Signature]
District Conservation Agent

Date 2-27-54

3-1-54