

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Form CP-3

Rev. 6-4-68

RECEIVED
STATE CORPORATION COMMISSION

SEP 01 1977
9-1-77
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -039 -20,398 -00-00 (of this well)

Operator's Full Name Citass Service Co.
Complete Address 209 E. William-700 Sutton Place Bldg., Wichita, Kansas
Lease Name Emigh "A" Well No. 1
Location SW NW SW Sec. 30 Twp. 5 Rge. (E) (W) 29
County Decatur Total Depth 4175'
Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A XX
Other well as hereafter indicated _____
Plugging Contractor Rains & Williamson Oil
Address Wichita, Kansas License No. _____
Operation Completed: Hour 3:25 A Day 31 Month 8 Year 1977

The above well was plugged as follows:

RTD 4175' 8 5/8 csg set 295' cwc 200 sk. Plg. Mat. 50-50 poz 6% total gel.
Gunned pits, circulated heavy mud, set 70 sk cmt plug at 1545' thru drill pipe.
Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 9-1-77

INV. NO. 5763-W