



15-039-30102-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 15 1970  
CONSERVATION DIVISION  
Wichita, Kansas

1-15-70

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Jim Beakey of Forbes Casing Pulling Co., Inc has this date requested permission to plug the following described well:

Mr. Beakey guarantees payment of the plugging fee.

Operator's full Name: Zenith Drilling Corporation, Incorporated,

Complete Address: 300 West Douglas, Wichita, Kansas.

Lease Name: Noone Well No. 1

Location: SW-NE-NW Sec. 27 Twp. 5 Rge. (E)(W) 26

County: Decatur Total Depth 3876' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Beakey was instructed to plug the well as follows:

248'--7" OD Surface casing, cement circulated with 135 Sx. (6 1/2" Hole).  
3857'--4 1/2" Production casing cemented on bottom with 100 Sx. Well plugged back to 3831'. Top perforations @ 3665'.

Push plug to 3625' sand to 3600' and set 3 Sx. cement with dump bailer.  
Pull 4 1/2" casing and squeeze well with 3 sacks hulls, 25 sacks gel and 70 Sx. cement, staged.

Very truly yours,

Conservation Division Agent