



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-039-00090-00-00

RECEIVED
STATE CORPORATION COMMISSION

FEB 26 1973

CONSERVATION DIVISION
Wichita, Kansas

2-26-73

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. D. B. Pulley of Rockhold Engineering, Inc., has this

date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: R. W. Shields,

Complete Address: 666 Fourth National Bank Bldg., Wichita, Kansas.

Lease Name: Feely Well No. C-1

Location: NE-SE-NW Sec. 6 Twp. 5 Rge. (E)(W) 26

County: Decatur Total Depth 3980' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Pulley was instructed to plug the well as follows:

231'--8 5/8" Surface casing, cement circulated with 175 Sx.

3740'--5 1/2" Production casing cemented on bottom with 150 Sx. Well plugged back to 3607'. Top of perforations @ 3558'.

Sand well back to 3500' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

W. L. Shields
Conservation Division Agent