



ROBERT B. DOCKING Governor  
DALE E. SAFFELS Chairman  
JULES V. DOTY Commissioner  
JAMES O. GREENLEAF Commissioner  
RAYMOND B. HARVEY Secretary  
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

AUG 23 1968

CONSERVATION DIVISION  
Wichita, Kansas

8-23-68

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. W. A. Walker of Rains & Williamson Oil Co. Inc. this date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Mull Drilling Company, Incorporated,

Complete Address: 1625 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Brown Well No. A-1

Location: CNW-NW Sec. 2 Twp. 5 Rge. (E)(W) 31

County: Rawlins Total Depth 4285 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Walker was instructed to plug the well as follows:

217'--8 5/8" Surface pipe, cement circulated.  
Top of Dakota section @ 1500'.

Circulate hole with heavy mud. Pull DP to 1725' and displace 100 Sx.  
ement thru DP. Pull DP to 245' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

Conservation Division Agent