



15-153-20018-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 29 1970
CONSERVATION DIVISION
Wichita, Kansas
12-29-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. D. B. Pulley of Forbes Casing Pulling Co., Inc., this date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Mull Drilling Company,

Complete Address: Box #349, Russell, Kansas.

Lease Name: Brown Well No. 1

Location: CSW-SE Sec. 2 Twp. 5 Rge. (E)(W) 31

County: Rawlins Total Depth 4280' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Pulley was instructed to plug the well as follows:

204'--8 5/8" Surface casing, cement circulated with 150 Sx.
4093'--4 1/2" Production casing cemented on bottom with 150 Sx. Well plugged back to 4055'. Top of cement @ 3950' (Temp. Survey). Push plug to 3900' sand to 3850' and set 3 Sx. cement with dump bailer. Squeeze well with 5 sacks hulls, 40 sacks gel and 150 Sx. cement, staged.

Very truly yours,

K. L. Nichols
Conservation Division Agent