



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 SEP 5 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 9-5-68

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Bob Barnes of Barnes & Sons Pipe Pulling Co. has this date requested permission to plug the following described well:

Mr. Barnes guarantees payment of the plugging fee.

Operator's full Name: Empire Drilling Company,

Complete Address: 650 4th National Bank Building, Wichita, Kansas.

Lease Name: Schmahl Well No. 1

Location: NW-NW-NW Sec. 9 Twp. 5 Rge. (E)(W) 31

County: Rawlins Total Depth 4211 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Barnes was instructed to plug the well as follows:

160'--8 5/8" Surface casing, cement circulated with 100 Sx.

4207'--5 1/4" Production casing cemented on bottom with 75 Sx.

Sand well back to 4190' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 35 sacks gel with 5 sacks hulls in initial gel and 130 Sx. cement staged.

Very truly yours,

*H. S. Piche*  
 Conservation Division Agent