

State of Kansas



15-153-20020-00-00

ROBERT B. DOCKING Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
DALE E. SAFFELS Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 6 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
5-6-68

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Marion Helberg of Helberg Oil Company has this date requested permission to plug the following described well:

Mr. Helberg guarantees payment of the plugging fee.

Operator's full Name: Helberg Oil Company,

Complete Address: Morland, Kansas.

Lease Name: G. P. Schmahl Well No. 2

Location: NE-SE-NE Sec. 8 Twp. 5 Rge. (E)(W) 31

County: Rawlins Total Depth 4180' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Helberg was instructed to plug the well as follows:

200'--8 5/8" Surface pipe, cement circulatory with 100 Sx.

Circulate hole with heavy mud. Pull DP to ~~1825'~~ 1825' and displace 100 Sx. cement thru DP. Pull DP to 215' and displace 20 Sx. cement thru DP.

Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

M. L. Nichols  
Conservation Division Agent