

State of Kansas



15-153-20012-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 17 1967

8-17-67

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Marion Helberg of Helberg Oil Company has this date requested permission to plug the following described well:

Mr. Helberg guarantees payment of the plugging fee.

Operator's full Name: Helberg Oil Company,

Complete Address: Box #32, Morland, Kansas.

Lease Name: G. P. Schmahl Well No. 1

Location: App. -NE-NE-NE Sec. 8 Twp. 5 Rge. (E)(W) 31

County Rawlins Total Depth 4175' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Helberg was instructed to plug the well as follows:

180' -- 8 5/8" Surface pipe, cement circulated with 80 Sx. Dakota section from 1480' to 1600'.

Circulate hole with heavy mud. Pull DP to 1620' and displace 80 Sx. cement thru DP. Pull DP to 210' and displace 30 Sx. cement thru DP. Pull DP. set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

A. L. Nichols
Conservation Division Agent