



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 4 1968
 CONSERVATION DIVISION
 Wichita, Kansas
 9-4-68

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Bill Walker of Rains & Williamson Oil Co. Inc. has this date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Company, Incorporated.

Complete Address: 1425 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Barnett Well No. 1

Location: App.-CSE-SE Sec. 29 Twp. 5 Rge. (E)(W) 31

County: Rawlins Total Depth 4190 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Walker was instructed to plug the well as follows:

218'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1525.

Circulate hole with heavy mud. Pull DP to 1750 and displace 100 Sx.
cement thru DP. Pull DP to 240' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent