



15-183-20030-00-00

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 9 1968
 CONSERVATION DIVISION
 Wichita, Kansas
 9-9-68

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Dean Ulrich of Murfin Drilling Company, has this date requested permission to plug the following described well:

Mr. Ulrich guarantees payment of the plugging fee.

Operator's full Name: Nadel-Gussman & Murfin Drilling Company,

Complete Address: 1714 First National Bank Building, Tulsa, Oklahoma.

Lease Name: Woerpel Well No. 1

Location: CSW-NW Sec. 23 Twp. 5 Rge. (E)(W) 31

County: Rawlins Total Depth 4220' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ulrich was instructed to plug the well as follows:

304'--8 5/8" Surface casing, cement circulated with 250 Sx.
Top of Dakota section @ 1525'.

Circulate hole with heavy mud. Pull DP to 1750' and displace 100 Sx.
cement thru DP. Pull DP to 340' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

W. L. Nichols
 Conservation Division Agent