



15-153-20027-00-00

ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAY 14 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 5-14-69

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Joe Clark of Southwest Csg. Pulling Co., has this date requested permission to plug the following described well:

Mr. Clark guarantees payment of the plugging fee.

Operator's full Name: Mull Drilling Company, Incorporated,

Complete Address: 1625 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Woerpel Well No. 3

Location: CNW-SW Sec. 13 Twp. 5 Rge. (E)(W) 31

County: Rawlins Total Depth 4206 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Clark was instructed to plug the well as follows:

216'--8 5/8" Surface casing, cement circulated with 150 Sx.  
4205'--4 1/2" Production casing cemented on bottom with 25 Sx. Top perforations @ 4044'.

Push plug to 4000', build sand bridge and set 3 Sx. cement with dump bailer.  
Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 130 Sx. cement and 130 Sx. cement staged.

Very truly yours,

Conservation Division Agent