



15-133-20019-00-00

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

300 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 14 1969
 CONSERVATION DIVISION
 Wichita, Kansas
 5-14-69

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Joe Clark of Southwest Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Clark guarantees payment of the plugging fee.

Operator's full Name: Mull Drilling Company, Incorporated.

Complete Address: 1625 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Woerpel Well No. 2

Location: CSE-SW Sec. 13 Twp. 5 Rge. (E)(W) 31

County: Rawlins Total Depth 4370' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Clark was instructed to plug the well as follows:

208'--8 5/8" Surface casing, cement circulated with 150 Sx.

4369'--4 1/2" Production casing cemented on bottom with 125 Sx. No plug back. Top perforations @ 4035' to 4037'.

Push plug to 4000', sand back to 3975' and set 3 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 35 sacks gel and 130 Sx. cement staged.

Very truly yours,

Conservation Division Agent