

6- 090465

9-25

54
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-153-20,782 -0000
NE NW NE /4 SEC. 04, 05 S, 31 W
4950 feet from S section line
1650 feet from E section line

Operator license# 30763 Lease Erickson well #61-4

Operator: Neil Wood Oil & Gas Properties County Rawlins

Address: P.O. Box 99130 Well total depth 4500 feet *146.25*
Lubbock, Texas 79499 Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 257 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Emphasis Oil Operations License# 8241

Address: P.O. Box 819 Russell, Kansas 67665

Company to plug at: Hour: 3:36 PM Day: 23 Month: September Year: 1991

Plugging proposal received from: John Collins

Company: Emphasis Oil Operations phone: 913-483-5345

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 2700 feet with 20 sacks Rat hole: 15 sacks

2nd plug @ 1890 feet " 100 " Mousehole: 15 sacks

3rd plug @ 305 feet " 40 "

4th plug @ 40 feet " wiper plug & 10 sks.

5th plug @ feet "

Plugging Proposal Received by: Edwin A. Schumacher P.I.R.T. III
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 3:00 PM, Day: 25, Month: September, Year: 1991

Actual plugging report: Hole reported plugged as above.
Order 200sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Elevation: 2941 GL, Anhydrite depth: 2684 - 2721 feet

Did Not penetrate Arbuckle, cemented by Allied Cementing Company

I did / did not [X] observe the plugging. Ed Schumacher

DATE 11-4-91
WFL. NO. 33583

Ed S.

Ed Schumacher P.I.R.T. III
(agent)

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 14 1991
10-14-91

CONSERVATION DIVISION
WICHITA, KS