

6 020501

4-5

API NUMBER 15- 039-20,845 - 00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

E/2 NE SW, SEC. 26, T 5 S, R 26 W/E

1980 feet from S section line

2970 feet from E section line

Lease Name Dwyer Well # 1

County Decatur 122.69

Well Total Depth 3775 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 205

TECHNICIAN'S PLUGGING REPORT

Operator License # 7448

Operator: Burch Exp
Name & Address: 11225 Edinborough Way
Parker, Co. 80134
303-841-9417

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Western Ks. Drilling License Number 4083

Address

Company to plug at: Hour: 5:00 PM Day: 5 Month: April Year: 19 89

Plugging proposal received from Jim Manley

(company name) (phone)

were: Order 190 sks 60/40 Poz 6% Gel 3% Cal Cl 1 sk F.C. and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis mud between all plugs with good circulation and no fluid loss.

Plugging Proposal Received by Gil Balthazor (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5:00PM Day: 5 Month: April Year: 19 89

ACTUAL PLUGGING REPORT Cir Mud

1st plug at 2120' w/25 sks

2nd plug at 1760' w/100 sks

3rd plug at 210' w/40 sks

4th plug at 40' w/10 sks w/wiper

15 sks in rathole

Remarks: Halliburton (If additional description is necessary, use BACK of this form.)

RECEIVED STATE CORPORATION COMMISSION 4-19-89 APR 19 1989

CONSERVATION DIVISION Wichita, Kansas

Observe this plugging.

INVOICED

Signed Gilbert Balthazor (TECHNICIAN)

DATE 4-24-89

INV. NO. 24463 4-5