

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-35211-00-00
Spot: W2NWNW Sec/Twnshp/Rge: 7-18S-9W
660 feet from N Section Line, 330 feet from W Section Line
Lease Name: HABIGER Well #: 2
County: RICE Total Vertical Depth: 3256 feet

Operator License No.: 31528
Op Name: KELSO, MIKE - OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

PROD Size: 5.5 feet: 3253 150 SX CMT
SURF Size: 8.625 feet: 200 165 SX CMT

105⁸²

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/21/2004 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTY ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-7397

Proposed Plugging Method: See actual report.

RECEIVED
KCC DISTRICT #2
DEC 30 2004
WICHITA, KS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 12/21/2004 11:45 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

Sanded open hole to 3200' and put 5 sacks of cement on top. Cut off 5-1/2" casing at 1702'. Pulled to 1200' and pumped 35 sacks of cement. Pulled casing to 850' and pumped 35 sacks of cement. Pulled to 250' and circulated cement to surface.

60/40 posmix with 4% gel.

Allied Cement #20604

Remarks:

Plugged through: CSG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

INVOICED
DATE 1-14-05
INV. NO. 2005061071