

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-21606-00-00  
Spot: NE Sec/Twnshp/Rge: 8-18S-7W  
3690 feet from S Section Line, 1780 feet from E Section Line  
Lease Name: YOST-TIMMONS Well #: 2  
County: RICE Total Vertical Depth: 3224 feet

Operator License No.: 8917  
Op Name: GUSTUS, DEAN DBA JD PRODUCTION  
Address: 701 MAIN  
GENESEO, KS 67444

PROD Size: 5.5 feet: 3222 100 SX CMT  
SURF Size: 8.625 feet: 395 300 SX CMT

# 10478

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/21/2004 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MONTY ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-7397

Proposed Plugging Method: See actual report.

RECEIVED  
KCC DISTRICT #2  
DEC 30 2004  
WICHITA, KS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL  
Date/Time Plugging Completed: 12/23/2004 12:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded open hole to 3150' and put 5 sacks of cement on top. Cut off casing at 2420'. Pulled to 1050' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled to 700' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled to 450' and circulated cement to surface.

60/40 posmix with 4% gel.

Allied Cement #20563

Perfs:

Top	Bot	Thru	Comments
3224			

Remarks:

Plugged through: CSG

District: 02

Signed

Virgil Clothier  
(TECHNICIAN)

INVOICED

DATE 1-14-05

INV. NO. 2005061070