

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-21906-00-00
Spot: SESENE Sec/Twnshp/Rge: 35-26S-5E
2898 feet from S Section Line, 269 feet from E Section Line
Lease Name: BISAGNO Well #: 6
County: BUTLER Total Vertical Depth: 2752 feet

Operator License No.: 6655
Op Name: CRAWFORD, GARRY F. DBA CRAWFO
Address: PO BOX 727
EL DORADO, KS 67042

PROD Size: 4.5 feet: 2750
SURF Size: 8.625 feet: 216

\$ 89 44

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/30/2004 2:30 PM
Plug Co. License No.: 32701 Plug Co. Name: C & G DRILLING, INC.
Proposal Rcvd. from: GERRY CRAWFORD Company: CRAWFORD PRODUCTION COMP Phone: (316) 321-3942

Proposed Plugging Method: 5 sxs btm; circ from 300' to surf; plugged back 2680'; hole in casing @ 300'.

RECEIVED
KCC DISTRICT #2
JAN 4 - 2005
WICHITA, KS

Plugging Proposal Received By: BILL JOHNSON WitnessType: NONE
Date/Time Plugging Completed: 09/30/2004 3:30 PM KCC Agent: BILL JOHNSON

Actual Plugging Report:

Perfs:

5 sacks common cement on bottom plug; 50 sacks of 60/40 posmix with 4% gel and 3% CaCl at 504'. 105 sacks from 300' to surface; circulated around. Will have to top off.

United #5735 -- Arrived on location at 4:00 pm; job completed.

Remarks:

Plugged through: CSG

District: 02

Signed *Bill Johnson*
(TECHNICIAN)

INVOICED
DATE 1-14-05
INV. NO. 2005061069