

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20716-00-00
Spot: E2NENW Sec/Twnshp/Rge: 29-17S-10W
4620 feet from S Section Line, 2970 feet from E Section Line
Lease Name: JANSSEN A Well #: 2
County: ELLSWORTH Total Vertical Depth: 3274 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH STREET
NEWTON, KS 67114

PROD Size: 5.5 feet: 3273 100 SX CMT
SURF Size: 8.625 feet: 465 170 SX CMT

#106 41

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/20/2004 12:00 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: EDWARD S NEMNICH Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: See actual report.

RECEIVED
KCC DISTRICT #2
DEC 30 2004
WICHITA, KS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 12/20/2004 2:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

Sanded perforations to 2780' and put 5 sacks of cement on top. Shot off 5-1/2" casing at 1300'. Pulled to 1250' and pumped 35 sacks of cement. Pulled casing to 950' and pumped 35 sacks of cement. Pulled casing to 575' and circulated cement to surface.

60/40 posmix with 4% gel.

Copeland Cement #24944

Remarks: TOP PERF AT 2830'.

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED

DATE 1-14-05

WELL NO. 2005061073