

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-01838-00-01  
Spot: NWSESE Sec/Twnshp/Rge: 25-17S-10W  
990 feet from S Section Line, 990 feet from E Section Line  
Lease Name: STUMPS Well #: 5  
County: ELLSWORTH Total Vertical Depth: 3270 feet

Operator License No.: 31528  
Op Name: KELSO, MIKE - OIL, INC.  
Address: PO BOX 467  
CHASE, KS 67524

PROD Size: 5.5 feet: 3269  
SURF Size: 8.625 feet: 500

#212<sup>0</sup>

Well Type: EOR UIC Docket No: E21055.2 Date/Time to Plug: 12/16/2004 1:00 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTY ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Sand off perfs to 2430' and put 5 sacks cement on top. Cut off casing. Pull to 1250' and pump 35 sxs cement; pull casing to 900' and pump 35 sxs cement; and pull to 550' and circulate cement to surface.

RECEIVED  
KCC DISTRICT #2  
DEC 30 2004

Plugging Proposal Received By: VIRGIL CLOTHIER  
Date/Time Plugging Completed: 12/16/2004 4:15 PM

WitnessType: PARTIAL  
KCC Agent: VIRGIL CLOTHIER

WICHITA, KS

Actual Plugging Report:

Sanded off perforations to 2400'; put 5 sacks of cement on top; and cut off casing at 1412'. Pulled to 1250' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled casing to 900' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled casing to 550' and circulated cement to surface.

60/40 posmix with 4% gel.

Allied Cement #20576

Perfs:

Top	Bot	Thru	Comments
2486	3231		

Remarks:

Plugged through: CSG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

INVOICED  
DATE 1-14-05  
INV. NO. 2005061071