

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-153-20,717-00-00 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR A. L. Abererombie, Inc. OPERATORS LICENSE NO. 5393

ADDRESS 801 Union Center, Wichita, KS 67202 PHONE # (316) 262-1841

LEASE (FARM) Briney "A" WELL NO. 1 WELL LOCATION E/2 W/2 SW/4 COUNTY Rawlins

SEC. 29 TWP. 5S RGE. 36 ~~EXX~~(W) TOTAL DEPTH 4940' PLUG BACK TD _____

Check One:

OIL WELL _____ GAS WELL _____ D & A X SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8 SET AT 364 CEMENTED WITH 275 SACKS

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL 1st plug at 3130' w/25 sx; 2nd plug at 2240' w/100 sx; 3rd plug at 380' w/40 sx; 4th plug at 40' w/10 sx; 10 sx. in mousehole, 15 sx. in rathole. All cement 60/40 posmix, 6% gel.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACC-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 11:00 p.m. 7-4-88

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Bill Craig, Sr.

RECEIVED
STATE CORPORATION COMMISSION

7-12-88
JUL 12 1988
PHONE # (316) 674-2876

ADDRESS Box 297, Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. CONSERVATION DIVISION
Wichita, Kansas
LICENSE NO. 5422

ADDRESS 801 Union Center, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Jack K. Wharton
(Operator or Agent)

DATE: July 11, 1988