

KANSAS

AP

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-20033-00-00

RECEIVED
STATE CORPORATION COMMISSION
SEP 4 1968
CONSERVATION DIVISION
Wichita, Kansas
9-4-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Rains & Williamson Oil Company, Incorporated,

Complete Address: 1425 Wichita Plaza Building, Wichita, Kansas.

Lease Name Barnett Well No. 1

Location App.-CSE-SE Sec. 29 Twp. 5 Rge. (E) (W) 31

County Rawlins Total Depth 4190

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 7:30 PM Day 2 Month 9 Year 1968

The Above well was plugged as follows:

218'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1525'.

Circulated hole with heavy mud. Pulled DP to 1756' and displaced 100 Sx. cement thru
DP from 1756 to 1430'. Pulled DP to 240' and displaced 20 Sx. cement thru DP from
240' to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 9/4/68
INV. NO. 8406-u