

KANSAS

Form CP-3
Rev. 6-26-62

AL STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-20030-00-00

RECEIVED
STATE CORPORATION COMMISSION
SEP 9 1968
CONSERVATION DIVISION
Wichita, Kansas
9-9-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Nadel-Gussman & Murfin,

Complete Address: 1714 First National Bank Building, Wulsa, Oklahoma.

Lease Name Woerpel Well No. 1

Location CSW-NW Sec. 23 Twp. 5 Rge. (E) (W) 31

County Rawlins Total Depth 4220'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Murfin Drilling, Company,

Address: 617 Union Center Bldg., Wichita, Kansas. License No.

Operation Completed: Hour 5:00 PM Day 6 Month 9 Year 1968

The Above well was plugged as follows:

304'--8 5/8" Surface casing, cement circulated with 250 Sx.
Top of Dakota section @ 1525'.

Circulated hole with heavy mud. Pulled DP to 1765' and displaced 100 Sx. cement thru
DP from 1765' to 1440'. Pulled DP to 340' and displaced 25 Sx. cement thru DP from
340' to 265'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *N. L. Dichele*
Well Plugging Supervisor

INVOICED

DATE 9/9/68
INV. NO. 8421-u